


FEB - 9 1979

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-169-20093-0000 CONSERVATION DIVISION  
WELL PLUGGING RECORD Wichita, Kansas

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Saline County, Sec. 18 Twp. 16 Rge. 1 E/W  
Location as "NE/CNW/SW" or footage from lines

S/2 SW NE

Lease Owner Rains & Williamson

Lease Name Mortimer Well No. 1

Office Address 435 Page Court, 220 W. Douglas, Wichita, KS

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Dry Hole

Date Well completed 1-29 1979

Application for plugging filed 1-29 1979

Application for plugging approved 1-29 1979

Plugging commenced 1-29 1979

Plugging completed 1-29 1979

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or

its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman

Producing formation Depth to top Bottom Total Depth of Well 2698

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	167	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with 65 vis. rotary mud from T.D. up to 160'. Put in plug 1/2 sack hulls and 20 sacks cement. Filled on up with rotary mud to 40'. Put in plug 1/2 sack hulls and 10 sacks cement. Put 2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Berentz Drilling Company

STATE OF Kansas COUNTY OF Greenwood, ss.

Jack Berentz (employer or operator) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 428, Eureka, Kansas 67045 (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of January, 1979

Judy C. Davis  
Judy C. Davis

Notary Public.

My commission expires April 6, 1982

15.169.20093.0000

LOG OF WELL

Mortimer #1  
S/2 SW NE  
Section 18-16-1W  
Saline County, Kansas

OPERATOR: Rains & Williamson Oil Company

CONTRACTOR: Berentz Drilling Company

Commenced with rotary 1-22-79

Completed with rotary 1-29-79

Casing: 8 5/8"--- 167' cemented with 140 sacks

Soil	3'
Shale & Shells	95
Lime & Shale	160
Lime with Shale Strks.	670
Lime & Shale	1220
Shale & Lime	1740
Shale, Lime & Sand	1900
Shale & Lime	2044
Lime Lansing, KC.	2543
Shale & Lime	2680
Lime Miss.	2698 R.T.D.

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 9 1979

CONSERVATION DIVISION  
Wichita, Kansas