

15-165-02236-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 26 Twp. 17S Rge. 17W (E) (W)

Location as "NE/CNW&SW&" or footage from lines: NE SW SE
Lease Owner: Frontier Oil Company
Lease Name: Erbes Well No. 1
Office Address: 1720 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): Gas
Date well completed: March 30 1962
Application for plugging filed: March 1 1966
Application for plugging approved: March 1 1966
Plugging commenced: March 2 1966
Plugging completed: March 2 1966
Reason for abandonment of well or producing formation: Non-commercial

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: Sept. 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Gilbert Lecker
Producing formation: Topeka Depth to top: 3005 Bottom: Total Depth of Well: 3578 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205	-0-
				4 1/2"	3577'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

800' feet for each plug set.
Pressured annulus between surface pipe and casing to 150# and the pressure held. Mixed 25 sz mud gel and pumped down casing. Put in plug and mixed 70 sz portland cement and pumped plug with the cement 800' down the casing. Maximum pressure 150#.

Note: The casing was two staged from 1124' to surface and the cement circulated to surface.

RECEIVED
CONSERVATION COMMISSION
11-2-66
NOV 2 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Hallburton
Address: Hays, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Richard D. Parker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard D. Parker
612 Street Russell H. Keane
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of November, 1966

Jean Hollan
Notary Public.

My commission expires 5-22-70

DRILLERS LOG

Wells No. 1

CASING RECORD: COMPANY: Frontier Oil Company DESCRIPTION: NE SW Q4
 8 5/8" 205' CONTRACTOR: Red Tiger Drilling Co. 28-175-178
 w/125 cc cement COMMENCED: March 22, 1962 Rush County,
 Kansas
 4 1/2" @ 2077 ELEVATION: 2036 DF
 w/275 cc cement COMPLETED: March 31, 1962 2041 RB
 TOTAL DEPTH: 3875'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & lime	0	120	
Shale	120	130	
Blue shale	130	205	
Shale sand	205	550	
Sand	550	600	
Sand Redbed	600	1115	
Anhydrite	1115	1150	
Shale & shells	1150	1340	
Redbed shale & shells	1340	1600	
lime & shale	1600	2340	
lime	2340	3225	
Granite Wash & lime	3225	3875	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 4 1965
 11-4-65
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 5th day of April, 1962.

Walter Deak
 Notary Public

My Commission Expires:
11-17-62