

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-1165-21311-0000

LEASE NAME Morse

WELL NUMBER #1

       Ft. from S Section Line

       Ft. from E Section Line  
SE SW SE

SEC. 8 TWP. 18S RGE. 18W (E) or (W)

COUNTY Rush

Date Well Completed       

Plugging Commenced 3-9-87

Plugging Completed 3-11-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frontier Oil Company

ADDRESS 1720 Kansas State Bank Bldg.  
Wichita, Kansas 67202

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed?        If not, is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	600'	none
				4-1/2"	3950'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Plugged off bottom with sand to 3790' and 4 sacks cement. Shot pipe @2800', 2600', 2400', 2200', pulled 4-1/2" casing to 1200', pumped 50 sacks cement, pulled up to 700', pumped 75 sacks cement, pulled rest of 4-1/2" and pumped 40 sacks cement to fill surface, 60/40 pos, 4% gel, 2% cc. Pulling Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R., Darrell KELso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 87

My Commission Expires:



Notary Public  
STATE CORPORATION COMMISSION

3-19-87  
**MAR 19 1987** Form CP-4  
Revised 07-86  
CONSERVATION DIVISION  
Wichita, Kansas