


15-051-20216-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 36 Twp. 11 Rge. (E) 19(W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Thunderbird Drilling, Inc.
Lease Name Jensen Well No. 1
Office Address 400 N. Woodlawn, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 11 19 68
Application for plugging filed August 4 19 69
Application for plugging approved August 5 19 69
Plugging commenced September 9 19 69
Plugging completed September 12 19 69
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production July 19 69
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Lansing Depth to top 3444 Bottom 3448 Total Depth of Well 3678 Feet
Show depth and thickness of all water, oil and gas formations. PBT D 3595

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Oil & Water	3444	3448	8 5/8"	221	0
				5 1/2	3677	2872

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3595-3400
5 sacks cement 3400-3360
Pumped 20 sacks gel mud and 5 sacks hulls down 8 5/8" followed by 70 sacks cement, then 5 sacks gel mud then 60 sacks cement. All cement contains 50% Pozzalin.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. I. Blincoe (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. I. Blincoe
400 N. Woodlawn, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 69

My commission expires April 28, 1973

Glenda J. Culver
Glenda J. Culver Notary Public.

DRILLERS LOG

JENSEN NO. 1

CASING RECORD:	COMPANY:	Thunderbird Drilling, Inc.	DESCRIPTION:
8-5/8" @ 221' w/150 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	NE NW SW Sec. 36-11S-19W Ellis County, Kansas
TOTAL DEPTH: 3678'	COMMENCED:	February 27, 1968	ELEVATION: 2095KB
	COMPLETED:	March 7, 1968	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	37	
Shale	37	982	
Dakota	982	1212	
Shale & Red Bed	1212	1428	
Anhydrite	1428	1470	
Shale	1470	1990	
Shale & Lime	1990	2340	
Lime & Shale	2340	3280	
Lime	3280	3380	
Lime & Shale	3380	3463	
Lime	3463	3678	5 1/2" @ 3677' w/100 sax

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 11th day of March, 1968.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1970.