


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 36 Twp. 11S Rge. 19 (E) (W)
Location as "NE/CNW%SW%" or footage from lines. S/2 NE/4 NE/4
Lease Owner. Wilkinson Drilling, Inc.
Lease Name Jensen Well No. 1
Office Address 1121 Union Nat'l. Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-16 19 57
Application for plugging filed 8-16 19 57
Application for plugging approved 8-16 19 57
Plugging commenced 8-16 19 57
Plugging completed 8-16 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set @ 600' W/25 Sacks cement.
Center plug set @ 280' W/15 sacks cement.
Top plug set @ 40' W/1/2 sack hulls, 10 sacks cement.
Job complete @ 8:30 P.M., August 16, 1957

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilkinson Drilling, Inc.
Address 1121 Union National Bldg. - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
1121 Union Nat'l. Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 57

Carolyn F. Moore
Notary Public.

My commission expires January 2, 1961.

PLUGGING
FILE SEC 36 T 11 R 19W
BOOK PAGE 39 LINE 5

WILKINSON DRILLING INCORPORATED

1121 UNION NATIONAL BUILDING
WICHITA 2, KANSAS

JENSEN #1

Company	- Wilkinson Drilling, Inc.	Location:	S/2 NE/4 NE/4, Sec. 36-11S-19W,
Contractor	- Company Tools		Ellis County, Kansas.
Commenced	- 8-2-57	Casing:	313.80' - 6 5/8"
Completed	- 8-16-57	Elevation:	2013 RB
Total Depth	- 3660'		

FIGURES INDICATE BOTTOMS OF FORMATIONS

Depth	Formation
0 - 60	Surface Soil & Post Rock
60 - 280	Shale & Clay
280 - 302	Blue Shale
302 - 770	Shale & Shells
770 - 1325	Shale, Shells & Sand
1325 - 1880	Shale & Shells
1880 - 2145	Shale & Lime
2145 - 2775	Lime & Shale
2775 - 3065	Shale & Lime
3065 - 3197	Lime & Shale
3197 - 3555	Lime
3555 - 3592	Conglomerate
3592 - 3605	Simpson Shale
3605 - 3624	Simpson Sand
3624 - 3660	Simpson Shale
3660 - T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Jensen #1, located in the S/2 NE/4 NE/4, Section 36-11S-19W, Ellis County, Kansas.

WILKINSON DRILLING, INCORPORATED

Walter M. Wilkinson
Walter M. Wilkinson

Subscribed and sworn to before me this 23rd day of August, 1957.

Lucas J. ...
Notary Public

My commission expires January 2, 1961.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 36 T 11 R 19W
BOOK PAGE 39 LINE 5