

KCC OIL/GAS REGULATORY OFFICES

Date: 07/18/13

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767
 Op Name: Ritchie Exploration, Inc.
 Address 1: Box 783188
 Address 2: _____
 City: Wichita
 State: KS Zip Code: 67278 -3188
 Operator Phone #: (316) 691-9500

API Well Number: 15-057-20902-00-00
 Spot: NE-SW-NW Sec 11 Twp 28 S Rng 23 E / W
 1700 Feet from N / S Line of Section
 985 Feet from E / W Line of Section
 GPS: Lat: 37.62640 Long: 99.81091 Date: 7/18/13
 Lease Name: Blew Well #: 1
 County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

None.

Findings:

8 5/8" was set @ 364' with 250 sx cement. 5 1/2" was set @ 5207' with 250 sx cement on the primary cementing job. Company opened the port collar @ 1388' Consolidated Oil Well Services, L.L.C. pumped 290 sx cement, circulating 20 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.
 60/40 pozmix, 6% gel, 1/4# floseal by Consolidated Oil Well Services, L.L.C.
 GPS converted footages are 1687' FNL & 1001' FWL.

KCC WICHITA
JUL 29 2013
RECEIVED

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric McLaren
 Eric McLaren

Retain 1 Copy District Office
 Send 1 Copy to Conservation Division
RECEIVED
 JUL 24 2013
 KCC DODGE CITY

Form: _____

Handwritten initials