

KANSAS STATE CORPORATION COMMISSION CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION

JUL 6 1960

CONSERVATION DIVISION Wichita, Kansas

TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NE SW NW Sec. 36 Twp. 11 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3668

I have this date completed supervision of plugging of:

Lease Name: Jensen Well No. A-1

Operator's Full Name: J. F. Darby Oil Co

Complete Address: Box 295 Plainville, Kans

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 29 Month 6 Year 60

The above well was plugged as follows:

8 5/8" 208' circulated with cement - 5 1/2" 3664' with 100 sax cement behind.

Filled with sand to 3650', set 4 sax cement with dump bailer, pulled 2990'

5 1/2" to 550', circulate hole with heavy mud through 5 1/2" at 550', displaced

20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement

through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to bottom

cellar.

Mudding and cementing by Halliburton Cementing Co .

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICE DATE 7-7-60 INV. NO. 1609-4