

K

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 007-201644-00-00 (of this well)

Operator's Full Name Gear Pet., Co.

Complete Address 1325 Vickers KTB&T Bldg., Wichita, Ks. 67202

Lease Name Spriggs Well No. 1

Location NW NW NE Sec. 34 Twp. 30s Rge. 11 (E) (W) X

County Barber Total Depth 3800

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 3:30 Pm. Day 17 Month 9 Year 1979

The above well was plugged as follows:

207' 8 5/8" casing w/160 sax cement. 4 1/2" casing set at 3798' w/100
sax cement. Preforated at 3748'-Sand back to 3700'-Top sand w/4 sax
mixed cement w/ dump bailer-Pull 3282' 4 1/2" casing-Allied mixed &
pumped 7 sax hulls-20 sax gel-100 sax 50/50 posmix cement w/4% gel to
top of casing. Shut in w/400# pressure.

RECEIVED
STATE CORPORATION COMMISSION
09-19-1979
SEP 19 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9-19-79
INV. NO. 489-W

Signed: [Signature]
Well Plugging Supervisor