

15-101-20090 0000 9

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1974
CONSERVATION DIVISION
Wichita, Kansas

05-20-1974

Operator's Full Name Okmar Oil Company,

Complete Address 1130 KSP&T Building, Wichita, Kansas.

Lease Name Cronic Well No. 1

Location NW-NW-NE Sec. 30 Twp. 17 Rge. (E) (W) 29

County Lane Total Depth 4620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kans. License No.

Operation Completed: Hour 3:30 AM Day 16 Month 5 Year 1974

The above well was plugged as follows:

308'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1210' and displaced 110 Cu. Ft. cement
thru DP from 1210' to 885'. Pulled DP to 315' and displaced 30 Cu. Ft. cement thru
DP from 315' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/21/74

INV. NO. 9161-W