

CP3

15101-00026-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 50-45

LOCATION CE6 NW-SW

SEC. 19 TWP. 17 RGE. 29 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease Floyd

Operator Jocelyn & Varn Address 310 K.F.H Bldg Wichita Ks.

Field County Lane

Total Depth 4431 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/8" @ 242' C.W.C. 5 1/2" @ 4427'
w/ 50 st Cem. Casing Perforated at 4337'. Sanded
hole to 4330' and dumped 5 st Cem. Shot
off and pulled 5 1/2" casing. Filled hole with
mud to 240' set rock bridge and run 20
st Cem. mud to 35' rock bridge and 10 st
Cem. to base of cellar

RECEIVED
STATE CONSERVATION COMMISSION
08-13-1954
AUG 13 1954

CONSERVATION DIVISION
Wichita, Kansas
H. Horner
District Conservation Agent

Date Aug 9, 1954

PLUGGING
FILE SEC 19 T 17 R 29W
BOOK PAGE 50 LINE 45