

15-101-190340001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 7 1965
07-07-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Oil and Gas Property Management,

Complete Address: 6th Floor C & I Life Building, Houston, Texas.

Lease Name Boomhower Well No. 1

Location CNE-SE Sec. 16 Twp. 17 Rge. (E) (W) 29

County Lane Total Depth Washdown 2900
Original 4712

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This well was a WASHDOWN

Plugging Contractor: Sargent's Casing Pulling Service,

Address: Box # 506, Liberal, Kansas. License No. 511

Operation Completed: Hour 11:00AM Day 2 Month 7 Year 1965

The Above well was plugged as follows:

265'--8 5/8" Surface pipe, cement circulated.
2829'--4 1/2" Production casing cemented with 200 Sx. Top of cement @ 2614'.
Top perforations @ 2772'.

Squeezed bottom of hole with 10 Sx. cement. Left top of cement @ 2700 WLM.

Pulled 4 1/2" to 660' and circulated heavy gel mud. Pulled 4 1/2" to 570' and
displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 230' and displaced 20 Sx.
cement thru 4 1/2". Pulled 4 1/2", set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar. (Recovered 2564' 4 1/2" Casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/7/65

INV. NO. 1421-W

Signed: H. L. Nichols
Well Plugging Supervisor