

KANSAS

Form CP-3
Rev. 6-4-68

P

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1978
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165-08773-0000 (of this well)

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name Thalheim Well No. 1

Location NE SW NW Sec. 26 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3570'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address Same as above License No.

Operation Completed: Hour 12:30 P Day 16 Month 8 Year 1978

The above well was plugged as follows:

Total Depth 3570' 8 5/8 csg set 214' cwc 135 sk.

5 1/2 csg set 2569' cw 175 sk cem. PFS (3028'-3038') Top. & (3564'-3569') LKC

5 1/2 csg DV tool set 1135' cwc 500 sk. No pipe recovered.

Mixed & pumped down 5 1/2 csg with 50 sk 50-50 poz 2% -displaced with 30 sk gel &

water W/300 lbs hulls, released 5 1/2 plug & capped with 50 sk 50-50 poz 2% & shutin.

FPP 500 lbs. SIP 0 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lee Maney
Well Plugging Supervisor

DATE 8-18-78
INV. NO. 7879-W