

3-11

1-080182
TO:

API NUMBER 15-101-21,562-6000

STATE CORPORATION COMMISSION NE-SE-NW, SEC. 25, T 17 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME PELTON WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE

OPERATOR LICENSE # 06113 WELL TOTAL DEPTH 4750 FEET ^{15' 38"}

OPERATOR: LANDMARK OIL EXPLORATION PRODUCTION CSG: SIZE 4 1/2 FEET 4595

NAME AND 1861 N Rock Rd, Ste 205 SURFACE CASING: SIZE 8 5/8 FEET 302

ADDRESS Wichita, KS 67206

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Allied Cementing LICENSE NUMBER

ADDRESS Box 628, Great Bend, KS 67530

COMPANY TO PLUG AT: HOUR: 8:45a DAY: 11 MONTH: 3 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) Allan Walker (PHONE) (316)792-3336

WERE: 100 lbs hulls, 25 sx cement, 13 sx gel, & cement from 2163 to surface.

fill 8 5/8"x5 1/2 annulus w/ cement

PLUGGING PROPOSAL RECEIVED BY Kevin Strube

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:15am DAY: 11 MONTH: 3 YEAR: 98

ACTUAL PLUGGING REPORT Allied pumped 100 lbs of hulls, 13 sx gel spacer, 165 sx cement, max psi 500 lbs, shut in 0 psi, well on vacuum, pressure tested 8 5/8" x 5 1/2" annulus, pumped 2 1/2 barrel 300 psi shut in. (3-12-98) Allied ran wireline tagged cement 300' down (3-13-98) Allied topped w/ 25 sx cement


3-17-98
92-11 V LI 8VH 866

REMARKS: Used 65/35 Pozmix 8% gel by Allied. No casing recovery. PORT COLLAR @ 2158' cemented with 32.5 SX cement.

I (DID/~~DO NOT~~) OBSERVE THIS PLUGGING.

SIGNED Kevin P Strube
(TECHNICIAN)

INVOICED


FORM CP-2/3

DATE 3-17-98

WV. NO. 50266

3-11

JUN 17 1998