

1 060915

Plyd. 12-13-86

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,346-0000

SW NW NE, SEC. 24, T 17 S, R 29 W/E

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Niedens Well # 1-24

Operator: Landmark Oil Exploration, Inc.

County Lane 150.48

Name & Address 110 South Main, Suite 510

Well Total Depth 4630 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 151 North Main, #700, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 13 Month: 12 Year: 19 86

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Company (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2782' GL
Anhydrite 2170-97'

1st plug at 2198' with 50 sx cement, 2nd plug at 1450' with 80 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 a.m. Day: 13 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2198' with 50 sx cement,

2nd plug at 1450' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED I (did not observe this plugging.

DATE 12-31-86

Signed Paul A. Luthi (TECHNICIAN) 12-19-1988

INV. NO. 15698 12-13