

1 050598

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,176-0000

NW SE NE, SEC. 21, T 17 S, R 29 W/E

3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Boomhower Well # 1

Operator: Mull Drilling Company, Inc.

County Lane 150.90

Name & Address P. O. Box 2758

Well Total Depth 4643 (Mississippi) feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Mallard Drilling Company License Number 5651

Address 405 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 13 Month: August Year: 1985

Plugging proposal received from Patty

(company name) Mallard (phone) 316-263-8218

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A Anhydrite 2214-2240'

1st plug at 2230' with 50 sx cement

2nd plug at 1600' with 50 sx cement

3rd plug at 780' with 50 sx cement

4th plug at 360' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey
cement to surface with 10 sx cement. (TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement
Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:50 am Day: 13 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement, 2nd plug at 1600' with 50

sx cement, 3rd plug at 780' with 50 sx cement, 4th plug at 360' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 7th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

R. W. L.

did not observe this plugging

RECEIVED
STATE CORPORATION COMMISSION

Signed Richard W. Lacey
(TECHNICIAN)

8-20-85

AUG 20 1985

INV. NO. 9693 SEP 11 1985

08-20-1985