

1080329

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-21,499-0000
SW SW SE SEC. 36, T 17 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BOOMHOWER WELL # 2-36

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 149.86

OPERATOR LICENSE # 5030

WELL TOTAL DEPTH 4611 FEET

OPERATOR: VESS OIL CORPORATION

PRODUCTION CSG: SIZE 4 1/2" @ 4612' WITH 185 SX

NAME AND 8100 E 22ND, BLDG. 300

SURFACE CASING: SIZE 8 5/8" @ 261' WITH 115 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SWIFT SERVICES LICENSE NUMBER 32382

ADDRESS PO BOX 466 NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 18 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM JOE RUPP

(COMPANY NAME) SWIFT SERVICES (PHONE) 785-798-2300

WERE: PORT COLLOR AT 2450' WITH 450 SX CEMENT. PERFS AT 4458-4532. FLUID LEVEL AT 1966' CASING LEAK AT APP. 4000'.

PUMP 50 SX CEMENT ON BOTTOM WITH 300# HULLS. GET TO 2100'. CEMENT FROM 2100' TO SURFACE.

PUMP 50 SX CEMENT DOWN ANNULUS.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 18 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT _____

PUMP 300# HULLS, 50 SX CEMENT, 10 SX GEL & 150 SX CEMENT. WELL ON VACUUM FELL TO APP.

650'. SHUT IN. PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CEMENT. PRESSURED UP TO 600#. SHUT IN.

Topped off with 35 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

Kevin D. Stued
(TECHNICIAN)

AUG 28 2000
8-28-00
CONSERVATION DIVISION
KANSAS

DATE 8/30/00

FORM CP-2/3

INV. NO. 2001060579

MD