

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21443-00-00  
Spot: CNESENW Sec/Twnshp/Rge: 36-17S-29W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: BOOMHOWER Well Number: 2  
County: LANE Total Vertical Depth: 4649 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DRIVE #204  
WESTMONT, IL 60559

Conductor Pipe: Size feet: \$151.09  
Surface Casing: Size 8.625 feet: 278  
Production: Size 5.5 feet: 4649  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/16/2002 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DOUG Company: MIDCO EXPLORATION Phone: (630) 655-2198

Proposed Plugging Method: CMT & HULLS FROM 4544-4100'. PUMP GEL TO 2500'. PUMP CMT FROM 2500-0'. CHECK BACKSIDE AND PUMP 25 SX IF NEEDED.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/16/2002 10:20 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4608'. PERFS AT 4546-49, 4551-4554, 4269-72, 4234-36, 4202-04, 4144-46'. ALTERNATE 2 COMPLETED FROM 2500' TO SURFACE. PUMP 50 SX CMT WITH 300# HULLS FOR BOTTOM PLUG. PUMP 18 SX GEL AND 200 SX CMT. PRESSURED TO 1500#. SHUT IN WITH 1000#. TIED ONTO BACKSIDE AND PRESSURED TO 500# AND HELD.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael J Maier  
(TECHNICIAN)

INVOICED  
DATE Jan 23-02  
INV. NO. 2002061279

RECEIVED  
1-22-02  
JAN 17 2002  
KCC WICHITA

Form CP-2/3