

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21409-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 36-17S-29W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease/Unit Name: BOOMHOWER Well Number: 1-36  
County: LANE Total Vertical Depth: 4640 feet

Operator License No.: 5030  
Operator Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 264 WITH 160 SX CMT  
Production: Size 4.5 feet: 4643 WITH 185 SX CMT  
Liner: Size \_\_\_\_\_ feet: 150.80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2000 11:25 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: PUMP 30 SX CMT AND 200# HULLS. PUMP GEL TO ANHYDRITE. PUMP CMT OT SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/06/2000 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4240-4553'. TOP HAS BEEN CEMENTED WITH 550 SX CMT FROM 2200' TO SURFACE. PUMP 35 SX CMT WITH 200# HULLS FOR BOTTOM PLUG. PUMPED 30 BBL GEL THEN 115 SX CMT. MAXIMUM PRESSURE 200#. WAS PUMPING BUT WENT ON VACUUM WHEN SHUT DOWN. TIED ONTO BACKSIDE AND PUMPED 50 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN WITH 100#. 12/08/00 TOPPED OFF WITH 65 SX CMT.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 2000  
12-14-00  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Michael J. Maier  
(TECHNICIAN)

INVOICED  
DATE 12/15/00  
INV. NO. 200106141

DEC 08 2000

Form CP-2/3