

1080288

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-21,300 ~~0000~~
SE SE NW SEC. 36, T 17 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BOOMHOWER WELL # 1

TECHNICIAN'S PLUGGING REPORT 12/30

COUNTY LANE 149.50

OPERATOR LICENSE # 5254

WELL TOTAL DEPTH 4600 FEET

OPERATOR: MIDCO EXPLORATION INC. PRODUCTION CSG: SIZE 4 1/2" @ 4594' WITH 175 SX

NAME AND ADDRESS 200 E 1ST STREET, SUITE 411 WICHITA, KS 67202 SURFACE CASING: SIZE 8 5/8" @ 331' WITH 190 SX

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT'S CASING PLUGGERS LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67905-0506

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 29 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SARGENT'S CASING PLUGGERS (PHONE) 316-624-7455

WERE: PERFS AT 4151-55 & 4184-90 CEMENT FROM 0' TO 2500' WITH 200 SX OF ATL CEMENT

PUMPED DOWN 4 1/2" WITH 20 SX CEMENT CLASS H WITH 200# HULLS. DISPLACED WITH 62 BBL HOLE

STAYED LOADED. TRY TO PULL CASING BUT FOUND OUT CASING WAS CEMENTED FROM 0' TO 2500'.

RAN TUBING TO 1250' SHUT DOWN. 12/30/99 PUMPED 20 SX CEMENT AT 1250', PULLED TUBING TO

650', PUMPED 15 SX, PULLED TUBING TO 350' PUMPED 30 SX CEMENT CIRCULATED CEMENT TO SURFACE

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 30 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT PUMPED DOWN 4 1/2" WITH 20 SX CEMENT CLASS H WITH 200# HULLS, DIS-

PLACED WITH 62 BBL HOLE STAYED LOADED. TRY TO PULL CASING BUT FOUND OUT CASING WAS CE-

MENTED FROM 0' TO 2500'. RAN TUBING TO 1250' SHUT DOWN. 12/30/99 PUMPED 20 SX CEMENT AT

1250', PULLED TUBING TO 650' PUMPED 15 SX CEMENT, PULLED TUBING TO 350' PUMPED 30 SX

CEMENT CIRCULATED CEMENT TO SURFACE.

REMARKS: USED CLASS H CEMENT BY SARGENTS. NO CASING RECOVERED.

INVOICED 1/10/00

I (DID) OBSERVE THIS PLUGGING.

DATE 1/10/00

SIGNED Kevin D. Strube (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

JAN 05 2000 CONSERVATION DIVISION Wichita, Kansas FORM CP-2

INV. NO. 061090