

To: 1 060787  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App C NE SW, SEC. 35, T 17 S, R 29 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,280-~~0000~~  
1790 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420

3370 feet from E section line

Operator: White & Ellis Drilling, Inc.  
Name & Address 401 E. Douglas, Suite 500  
Wichita, KS 67202

Lease Name Riley "A" Well # 1

County Lane Lane 151.13

Well Total Depth 4650 Mississippi feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 28 Month: January Year: 19 86

Plugging proposal received from Judy Steiben

(company name) White & Ellis (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Elevation NA  
Anhydrite 2183'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:45 pm Day: 28 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2210' with 50 sx cement, 2nd plug at 1340' with 80 sx

cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1986

01-30-1986

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED** do not observe this plugging.

DATE JAN 31 1986

INV. NO. 12226

Signed Paul A. Luthi  
(TECHNICIAN)