

To: 1. 090724  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-21,726-0000  
SW SW SW, SEC. 31, T 17 S, R 29 W X  
330 feet from S section line  
330 feet from W X section line

TECHNICIAN'S PLUGGING REPORT 8-21  
Operator License # 6622

Lease Name Cramer Farms Well # 1  
County Lane 149.82

Operator: Jason Oil Company  
Name & Address: P.O. Box 701  
Russell, KS 67665-0701

Well Total Depth 4610 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 245.5

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Discovery Drilling, Inc. License Number 31548  
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 11 p.m. Day: 20 Month: 8 Year: 1996

Plugging proposal received from Tom Alm  
(company name) Discovery Drilling, Inc. (phone) 913-623-2920

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2230'  
1st plug at 2230' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,  
3rd plug at 675' with 40 sx cement, 4th plug at 275' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:45 a.m. Day: 21 Month: 8 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement,  
2nd plug at 1250' with 80 sx cement, 3rd plug at 675' with 40 sx cement,  
4th plug at 275' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 22 1996  
08-22-1996  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby agree to observe this plugging.

DATE AUG 28 1996  
INV. NO. 43670  
8-21

Signed \_\_\_\_\_  
(TECHNICIAN)