

1050574

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Operator: American Energies Corporation
Name & Address 575 Fourth Financial Center
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 10:00 am Day: 10 Month: July Year: 19 85

Plugging proposal received from Daryl John

(company name) Hembree (phone) 913-798-3408

were: 4 1/2" at 4643' PBTM 4425' Perfs at 4038-4375

1st plug sand back to 3985' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 pm Day: 10 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3985' and dumped 4 sx cement on top
of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION

09-22-1985

FJH 22 1085

Maximum pressure 600 psi and shut in 150 psi CONSERVATION DIVISION

Remarks: Recovered 921' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED (Initials or stamp) observe this plugging.

DATE 7-24-85

INV. NO. 9085

Signed Richard W. Lacy
(TECHNICIAN)