

10-15

143
R

To: 1 120641
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,603-0000
NE SE NW, SEC. 16, T 17 S, R 29 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 N. Market, Suite 205
Wichita, KS 67202

Lease Name Boomhower "C" Well # 1
County Lane 140.59
Well Total Depth 4326 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 15 Month: 10 Year: 19 91

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2195-2224'
1st plug at 2230' with 50 sx cement, 2nd plug at 1100' with 50 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 270' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 a.m. Day: 15 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement,
2nd plug at 1100' with 50 sx cement,
3rd plug at 600' with 50 sx cement,
4th plug at 270' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-22-1991
OCT 22 1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-4-91
INV. NO. 33566

Signed Duane Rankin (TECHNICIAN)