

Rec'd - 12-11-1985

1 030582

API NUMBER 15-101-21, 248-000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NW SW SEC. 16, T 17 S, R 29 NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from S section line

4890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Boombower Well # 1

Operator: Petroleum Inc.

County LAWE 150.05

Name & Address 300 W. Douglas

Well Total Depth 4617 miss feet

Suite 800

Conductor Pipe: Size _____ feet

Wichita Ks. 67202

Surface Casing: Size 8 7/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilg. Inc. License Number 5422

Address 801 Union St. Wichita Ks. 67202

Company to plug at: Hour: 11:00 AM Day: 23 Month: 11 Year: 19 85

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 793-8491

were: fill hole w/ heavy mud and spot cement plugs through tubing -

1st plug set @ Base Anhydrite w/ 50sx

2nd " " " 50' Below Base of Cheyenne sd. w/ 70sx -

3rd " " " 30' Below Base Surface Pipe w/ 40sx

4th Built solid bridge @ 40' => fill w/ cement to 0' w/ 10sx -

6th Circ Rattake w/ 15sx Plugging Proposal Received by S. Remond

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 PM Day: 23 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Filled Hole w/ mud and spotted cement through drill pipe:

1st plug @ 2245' w/ 50sx

2nd " " 1250' w/ 70sx Anhyd. 2245

3rd " " 248 w/ 50sx Elev. 2827 KB

4th Solid Bridge @ 40' => fill w/ cement to 0' w/ 10sx -

6th Circ Rattake w/ 15sx

Remarks: By Sun - #340731 60/40 Perm 6% gel. no cu.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did/did not) observe this plugging.

DATE DEC 11 1985

Signed Steve Remond
(TECHNICIAN)

INV. NO. 11453

11-23