

CP4

WELL NAME Krug

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 12 TWP. 18S RGE. 18 (E or W)

COUNTY Rush

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601

PHONE(S) (913) 625-6374 OPERATORS LICENSE NO. 3456

Date Well Completed 4/9/96

Character of Well D&A

Plugging Commenced 6:00PM 4/9/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8:30PM 4/9/96

The plugging proposal was approved on 4/9/96 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, -GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>4-30-96</u>	<u>96</u>	<u>0</u>	<u>1240</u>	<u>8 5/8</u>	<u>1240.26</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each s  
1st Plug @ 1280' w/50sks Circulated 1st Plug 15 Minutes w/48 Vis Mud  
2nd Plug @ 730' w/50sks Plugs displaced with mud  
3rd Plug @ 40' w/10sks Total 135sks 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing  
10sks In Mouse Hole 15sks In Rat Hole Completed @ 8:30PM 4/9/96

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

EDGAR L. GLASSMAN (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac  
statements, and matters herein contained and the log of the above-described well as filed i  
the same are true and correct, so help me God.

(Signature) Edgar Glassman

(Address) P.O. Box 458; Hays, KS

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of April, 19 96

Linda K Pfannenstiel  
Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM

