

1 030458

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,303-0000C SE NW, SEC. 24, T 19 S, R 20 (W)X3300 feet from S section line3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151Lease Name Schank Well # 1-24Operator: Gear Petroleum Co., Inc.County Rush 112.06

Name &

Address 300 Sutton PlaceWell Total Depth 3448 feetWichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 588Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302Address 1720 Kansas State Bank Building, Wichita, KS 67202Company to plug at: Hour: 3:00pm Day: 4 Month: July Year: 19 85Plugging proposal received from Walt Oden(company name) Red Tiger (phone) 316-263-2371

Elevation

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1388-1418'1st plug at 1418' with 50 sx cement2nd plug at 620' with 40 sx cementsolid bridge3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement5th plug to circulate rat hole with 15 sx cement.Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XOperations Completed: Hour: 5:10 pm Day: 4 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1418' with 50 sx cement, 2nd plug at 620' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel

INVOICED

If additional description is necessary, use BACK of this form.)

I (XXX / did not) observe this plugging.DATE 7-18-85INV. NO. 8967Signed Steve Durrant

(TECHNICIAN)