

To: 1 031228  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-15

API NUMBER 15- 165-21,630-~~0000~~

W/2 SW SE, SEC. 22, T 19 S, R 20 W/E  
660 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Lease Name Price Well # 1-22

Operator: Ensign Operating Co.

County Rush 144.62

Name: Ensign Operating Co.

Address 621 17th St., Ste. 1800

Well Total Depth 4450 feet

Denver, CO 80293

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 666

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Duke Drilling License Number 5929

Address 310 W. Central, Ste. 117, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 15 Month: 5 Year: 19 93

Plugging proposal received from Gary Pugh

(company name) Duke Drilling (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1458'

1st plug at 1470' with 50 sx cement, 2nd plug at 690' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 11:45 a.m. Day: 15 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,

2nd plug at 690' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

(XXX) did not observe this plugging.

DATE 5-26-93

INV. NO. 37761

5-15

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

5-19-93  
MAY 19 1993

CONSERVATION DIVISION  
Wichita, Kansas

EFFECTIVE DATE: 10-19-93

DISTRICT # 1  
36A7... Yes... No

State of Kansas

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 165-21,630-0000 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 04 19 93  
month day year

Section 22 Twp 19 S. Rg 20 XX West

OPERATOR: License # 04782  
Name: Ensign Operating Co.  
Address: 621 17th Street, Suite 1800  
City/State/Zip: Denver, Colorado 80293  
Contact Person: J.C. Simmons  
Phone: 303-293-9999

660 feet from South /XXXX line of Section  
2310 feet from East /XXXX line of Section  
IS SECTION XX REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5929  
Name: Duke Drilling

County: Rush  
Lease Name: Price Well #: 1-22

Field Name: Wildcat

Is this a Prorated/Spaced Field? yes XX no

Target Formation(s): Mississippian

Nearest lease or unit boundary: 350'

Ground Surface Elevation: 2243 feet MSL

Water well within one-quarter mile: yes XX no

Public water supply well within one mile: yes XX no

Depth to bottom of fresh water: 400

Depth to bottom of usable water: 480 600

Surface Pipe by Alternate: XX 1 2

Length of Surface Pipe Planned to be set: 640 620

Length of Conductor pipe required: N/A

Projected Total Depth: 4450'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:

... well XX farm pond ... other

DWR Permit #: \_\_\_\_\_

Will Cores Be Taken? yes XX no

If yes, proposed zone: \_\_\_\_\_

Well Drilled For: Well Class: Type Equipment:

XX Oil Enh Rec Infield XX Mud Rotary

Gas Storage Pool Ext. Air Rotary

OWWO Disposal XX Wildcat Cable

Seismic: # of Holes Other

Other

If OWWO: old well information as follows:

Operator:

Well Name:

Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes XX no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 10/14/93

AFFIDAVIT

620' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101

Pusher Conroy Pugh  
SPUD DATE May 6-1993 INIT. GB  
LENGTH SURFACE PLANNED 620'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8 @ 666 CONDUCTOR  
ANHYDRITE T- 1458 B- ELEVATION  
TD 4450 FORMATION MISS  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
1 Anhydrite Base @ 1490 Ft. W/ 50 SX  
1/2 Base Anyh. @ Ft. W/ SX  
1/2, 1/2 Plug @ Ft. W/ SX  
2 Bottom Surface @ 690 Ft. W/ 50 SX  
3 40' Plug @ 40- Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELL Small SX (Irr. Well Pond Hauling)  
TECHNICIAN 50 DATE  
TYPE OF CEMENT 60/40 Port 60%  
STARTING TIME 10:00 (AM/PM) DATE 5-15-93  
COMPLETION TIME 11:45 (AM/PM) DATE 5-15-93  
CEMENT COMPANY ALLIED