

1 120913

4-7

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,651-0000

N/2 NE NW, SEC. 21, T. 19 S, R. 20 W.  
330 feet from ~~NY~~ section 11-  
1980 feet from ~~WX~~ section 11-

TECHNICIAN'S PLUGGING REPORT

Operator License # 31283

Lease Name Bannister Well # 1

Operator: Argent Exploration, Inc.

County Rush

Name & Address 110 S. Main, Ste. 810

Well Total Depth 4450 144.62 ft

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet .297

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 4:30 p.m. Day: 7 Month: 4 Year: 19 94

Plugging proposal received from Greg Davison

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1514-45'

1st plug at Base of Anhydrite with 50 sx cement,

2nd plug at 820' with 50 sx cement, 3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7 p.m. Day: 7 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1550' with 50 sx cement,

2nd plug at 820' with 50 sx cement,

3rd plug at 350' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 12 1994 4-12-94

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 4-19-94 INV. NO. 40312

EFFECTIVE DATE: 3-26-94

DISTRICT # 1

SEAL Yes No

Expected Spud Date March 24 1994

OPERATOR: License # 31283

Name: ARGENT EXPLORATION, INC.

Address: 110 S. MAIN, SUITE 810

City/State/Zip: WICHITA, KANSAS 67202

Contact Person: JAMES L. RHEEM

Phone: 316-262-5111

CONTRACTOR: License # 6039

Name: L.D. DRILLING, INC.

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec ... Infield X Mud Rotary

... Gas ... Storage ... Pool Ext. ... Air Rotary

... OGW ... Disposal X Wildcat ... Cable

... Seismic: ... # of Holes ... Other

If OGW: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no

If yes, true vertical depth: Bottom Hole Location:

Exp. 9/21/94

The undersigned hereby affirms that the drilling completion and eventual plugging of this well will comply with...

State of Kansas NOTICE OF INTENTION TO DRILL

165-21,651-2

Must be approved by the K.C.C. five (5) days prior to commencing well

Spot N/2 NE... NW... Sec .21. Twp 19.. S. Rg .20.. East West

330' feet from South / North line of Section 1980' feet from East / West line of Section

IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: RUSH

Lease Name: BANNISTER Well #: 1

Field Name: UNNAMED

Is this a Prorated/Spaced Field? ... yes X no

Target Formation(s): MISSISSIPPIAN/CHEROKEE

Nearest lease or unit boundary: 330'

Ground Surface Elevation: 2291' feet MSL

Water well within one-quarter mile: ... yes X no

Public water supply well within one mile: ... yes X no

Depth to bottom of fresh water: 250'

Depth to bottom of usable water: 810'

Surface Pipe by Alternate: ... 1 X 2

Length of Surface Pipe Planned to be set: 270'

Length of Conductor pipe required: None

Projected Total Depth: 4400'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations: ... well X farm pond other

Oil Permit #: Will Cores Be Taken?: ... yes XX no

If yes, proposed zone: 270' Alt. II Req.

AFFIDAVIT



Pusher: INIT. LENGTH SURFACE PLANNED 300' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2" @ 297' CONDUCTOR ANHYDRITE T- 1514 B-45 ELEVATION TD 4450' FORMATION TYPE RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1550' Ft. W/ SX 1/2 Base Anyh. @ 820 Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 350 Ft. W/ SX 40' Plug @ 40 Ft. W/ SX RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN DR DATE 4-7-94 TYPE OF CEMENT DATE 4-7-94 STARTING TIME 4:30 (AM/PM) DATE 4-7-94 COMPLETION TIME 12:00 (AM/PM) DATE 4-7-94 CEMENT COMPANY Applied Drilling saw all