

To: 1120985
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
260 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-9

API NUMBER 15-165-21,671-0000
N/2 N/2
S/2 SE, SEC. 19, T 19 S, R 20 W/EX
1155 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097
Operator: Martin Oil Producers, Inc.
Name & Address 150 N. Main, Ste. 1010
Wichita, KS 67202

Lease Name Schlereth-Bruntz Well # 2
County Rush
Well Total Depth 4430 ^{143.98} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 7 p.m. Day: 9 Month: 11 Year: 19 94

Plugging proposal received from Mike
(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1496-1525'
1st plug at 1530' with 50 sx cement,
2nd plug at 630' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 9 p.m. Day: 9 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,
2nd plug at 630' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 12-5-94
INV. NO. 41798

165-21,671-0000 **MISSE OF INTERESTION TO DRILL** **SURFACE CEMENTS, ALT. I** 671
 Must be approved by the K.C.C. five (5) days prior to commencing well
 N/2 S/2 SE/4 19 19 20 East
 Sec Twp S. Rg X West

SEAT No. Y
 Expected Spud Date Oct 15 1994
 month day year

OPERATOR: License # 5097
 Name: Martin Oil Producers, Inc.
 Address: 150 N. Main, #1010
 City/State/Zip: Wichita, KS 67202
 Contact Person: Joe Moreland
 Phone: 316-264-0352

CONTRACTOR: License # 5418
 Name: Allen Drilling Co.

Well Drilled For: Well Class: Type Equipment:
 Oil Enh Rec Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OUVG Disposal Wildcat Cable
 Seismic: # of Holes Other
 Other
 If OWNED: old well information as follows:
 Operator:
 Well Name:
 Comp. Date: Old Total Depth

1155 feet from South North line of Section
1320 feet from East West line of Section
 IS SECTION REGULAR IRREGULAR?
 (NOTE: Locate well on the Section Plat on Reverse Side)
 County: Rush
 Lease Name: Schlereth-Bruntz Z
 Field Name: Schadel NE
 Is this a Prorated/Spaced Field? yes no
 Target Formation(s): Cherokee Sand, Miss.
 Nearest lease or unit boundary: 1155
 Ground Surface Elevation: 2285 feet MSL
 Water well within one-quarter mile: yes no
 Public water supply well within one mile: yes no
 Depth to bottom of fresh water: 220 360
 Depth to bottom of usable water: 375 540
 Surface Pipe by Alternate: 1
 Length of Surface Pipe Planned to be set: 400 560
 Length of Conductor pipe required: none
 Projected Total Depth: 4425
 Formation at Total Depth: Miss. Osage
 Water Source for Drilling Operations:
 well farm pond other
 DWR Permit #:
 Will Cores Be Taken?: yes no
 If yes, proposed zone:
 560' Alt. I Req.

Directional, Deviated or Horizontal wellbore? yes no
 If yes, true vertical depth:
 Bottom Hole Location:

Exp. 4/7/95

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
 It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to spudding of well;
2. A copy of the approved notice of intent to drill shall be posted on each drilling rig;
3. The minimum amount of surface area...

RECEIVED
 STATE CORPORATION COMMISSION
 10-7-94
 OCT 17 1994

Pusher Mike INIT. OR
 SPUD DATE 10-21-94
 LENGTH SURFACE PLANNED 560'
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE _____
 SURFACE PIPE 8 1/2 @ 599 CONDUCTOR _____
 ANHYDRITE T- 1494 B- 1525 ELEVATION _____
2300 FORMATION Miss
 TD 4430
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
 Arbuckle Plug @ _____ Ft. W/ _____ SX
 Hug./Council @ _____ Ft. W/ _____ SX
 Anhydrite Base @ 1530 Ft. W/ 50 SX
 1/2 Base Anhy. @ _____ Ft. W/ _____ SX
 1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
 Bottom Surface @ 630 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
 WATER WELL _____ SX (Irr. Well _____ Pond _____)
 Hauling _____
 TECHNICIAN OR DATE 11-3-94
 TYPE OF CEMENT 60-40 670
 STARTING TIME 1:00 (AM/PM) DATE 11-9-94
 COMPLETION TIME 9:00 (AM/PM) DATE 11-9-94
 CEMENT COMPANY A Halliburton