

To: ¹ 071034 3-12 App.
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,444-0000 129
W/2 W/2 NE NW, SEC. 4, T. 19 S, R. 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: KCC
Name: _____
Address: _____

4700 feet from S section line
3800 feet from E section line
Lease Name Frank Well # 2
County Rush
Well Total Depth 4330 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒ X

Other well as hereinafter indicated _____

Plugging Contractor KCC License Number _____

Address 304 W. McArtor, Dodge City, KS 67801

Company to plug at: Hour: 2:30 p.m. Day: 12 Month: 3 Year: 19 92

Plugging proposal received from Dan Goodrow

(company name) KCC (phone) 913-798-3338

Notes: Well has a 50 sx plug at 1460'.

Drill out 10 sx plug placed at 40', drill out 40 sx plug placed at 390'. Pump through tubing 80 sx cement at 750', 30 sx at 390', and 10 sx at 40' with heavy gel spacers.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ X Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 12 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug ran tubing to 750', pumped 80 sx cement at 750',

2nd plug pumped 35 sx cement at 390',

3rd plug pumped 5 sx cement at 30'.

Remarks: Used 120 sx 60/40 Pozmix 6% gel total by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed

(TECHNICIAN)