

To: 1 052073
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-165-21,427-0000
NE NE SE, SEC. 10, T 19 S, R 20 W/E
2310 feet from S section line
330 feet from E section line

10-7
TECHNICIAN'S PLUGGING REPORT
Operator License # 5205
Operator: Mid-Continent Energy Corporation
Name & Address: 105 S. Broadway, #900
Wichita, KS 67202

Lease Name Lyda-Web A Well # 1
County Rush 139.75
Well Total Depth 4300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service, Inc. License Number 6454
Address P.O. Box 384, Ness City, KS 67560-0384

Company to plug at: Hour: 9 a.m. Day: 7 Month: 10 Year: 1996

Plugging proposal received from Kent Roberts
(company name) Mid-Continent Energy Corp. (phone) 316-265-9501

Work: 4 1/2" at 4299' w/500 sx cement, PBD 4299', Perfs at 4188-92', DV at 1438-0' w/400 sx cement
1st plug pump 200 lbs. hulls and 35 sx cement down 4 1/2",
2nd plug at 1400' with 30 sx cement, 3rd plug at 700' with 20 sx cement,
4th plug at 300' with 20 sx cement, 5th plug at 40' with 10 sx cement.

10
5
26

Plugging Proposal Received by Richard Ladey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 7 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 35 sx cement.
Top of cement 2000'.

Plugs spotted through tubing:
2nd plug at 1411' with 30 sx cement,
3rd plug at 719' with 20 sx cement,
4th plug at 313' with 20 sx cement, 5th plug at 40' with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
OCT 17 1996
DATE _____
INV. NO. 46713

Signed Richard W. Ladey (TECHNICIAN)