

1060311

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,241-0000

SW SE SW, SEC. 10, T 19 S, R 20 W/EX
330 feet from ~~NXX~~ SE Corner of section line
3630 feet from ~~NXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5710

Lease Name Web Well # 2

Operator: Energex, Inc.

County Rush

Name & Address 1660 Lincoln, Suite 1650

Well Total Depth 4216 137.02 feet

Denver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor All-Star Drilling, Inc. License Number 8804

Address 2734 Colonial Street, Bl. Hays, KS 67601

Company to plug at: Hour: 2:00 am Day: 20 Month: August Year: 19 84

Plugging proposal received from Linus Sanders

(company name) All-Star (phone) 913-625-4800

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1300' with 50 sx cement

2nd plug at 600' with 40 sx cement

3rd plug at 420' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthie

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 am Day: 20 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1300' with 50 sx cement, 2nd plug at 600' with 40 sx

cement, 3rd plug at 420' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx

cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1984

8-29-84
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form)

INVOICED

did not observe this plugging.

DATE 8-29-84

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 3426

OCT 02 1984