

121

070694

API NUMBER 15- 165-21.477-0000

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NE SE, SEC. 26, T 18 S, R 18 W/R

2310 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Barron Well # 6

Operator: Frontier Oil Company
Name & Address 125 North Market, Suite 1720
Wichita, KS 67202

County Rush 123.83

Well Total Depth 3810 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1120

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank & Trust Building, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 24 Month: 6 Year: 19 89

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1985'
Anhydrite 1109-49'

1st plug at 1130' with 50 sx cement, 2nd plug at 650' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 a.m. Day: 24 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1130' with 50 sx cement,

2nd plug at 650' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1989
6-29-89
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 7-5-89

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 25158

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 6 19 89
month day year

C.N/2.NE SE.. Sec 26.. Twp 18 S, Rg 18 X East West
2310 feet from South line of Section
660 feet from East line of Section
(Note: Locate well on Section Plat Below)

OPERATOR: License # 5140
Name: Frontier Oil Company
Address: 125 N. Market, Ste. 1720
City/State/Zip: Wichita, Kansas 67202
Contact Person: George A. Angle
Phone: 316-263-1201

County: Rush
Lease Name: Barron Well #: 6
Field Name: Rush Center South
Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330
Ground Surface Elevation: N/A feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 200
Depth to bottom of usable water: 550
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe Planned to be set: 1125
Length of Conductor pipe required: N/A
Projected Total Depth: 3730
Formation at Total Depth: ARB
Water Source for Drilling Operations:
X well pump out of creek farm pond ... other

CONTRACTOR: License #: 5302
Name: Red Tiger Drilling Company

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... OMO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If OMO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #: N/A
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Spud 6-17-89

Surf 1120 +/- 8 5/8

600' Alt. I Req.

PUSHER Pat Waggoner
TD 3810 **FORMATION**
SURFACE PIPE 8 5/8" @ 1120'
ANHYDRITE 1149' **ELEVATION** 1985'
STARTING TIME & DATE 7:00 AM 6-24-89
COMPLETION TIME & DATE 8:30 AM 6-21-89
1st PLUG @ Arb **FT. W/** 50 **SX**
2nd PLUG @ 1130 **FT. W/** 50 **SX**
3rd PLUG @ 650 **FT. W/** 40 **SX**
4th PLUG @ 40 **FT. W/** 10 **SX**
RAT HOLE CIRCULATED W/ 15 **SX**
MOUSE HOLE CIRCULATED W/ — **SX**
WATER WELL PLUGGED W/ — **SX**
CEMENT COMPANY Allied
TECHNICIAN D.G.

STATE CORPORATION COMMISSION
RECEIVED
JUN 29 1989
6-29-89
CONSERVATION DIVISION
Wichita, Kansas
ad within

5280	1980
4950	1650
4620	1320
4290	990
3960	660
3630	330
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.

18
18W