

1-120973

9-22-94

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: 15-165-21,482-0000

E/2 NE SE /4 SEC. 26, 18 S, 18 W
1980 feet from S section line
330 feet from E section line

Operator license# 5140

Lease Barron well # 7

Operator: Frontier Oil Company

County Rush

Address: 125 N. Market, Ste. 1720
Wichita, KS 67202

Well total depth 3739 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe: 8 5/8 inch @ 1125 feet

121.51

Aband. Oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Co., Inc. License#

Address: P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: September Year: 1994

Plugging proposal received from: Richard Parker

Company: Frontier Oil Company Phone: 913-483-5348

Were: 4 1/2" at 3734' w/150 sx cement

1st plug set CIBP at 3630' in 4 1/2" casing. Pressure 4 1/2" casing to 500#.

2nd plug perforate 4 1/2" casing at 1136' and circulate cement with 200 sx cement.

Plugging Proposal Received by: Duane Rankin

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 10:30 a.m. Day: 22 Month: September Year: 1994

RECEIVED
KANSAS CORPORATION COMMISSION

Actual plugging report:

1st plug set CIBP at 3630' in 4 1/2" casing.

Pressured 4 1/2" casing to 500#.

2nd plug perforated 4 1/2" casing at 1135-36' and circulated cement from 1136' with 200 sx cement.

SEP 27 1994
9-27-94
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered no casing.

I did [] / did not [] observe the plugging.

Duane Rankin

(agent)

Form CP-2/3

INVOICED

DATE 9-28-94

INV. NO. 41294

[Handwritten mark]