

1 040548

6-30

237

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 165-21,562-0000

NE NW NE, SEC. 26, T 18 S, R 18 W/EX

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Deighton Well # 2

Operator: J.A. Allison

County Rush 124.57

Name & Address 300 W Douglas, Suite 305

Well Total Depth 3833 feet

Wichita, KS 67202-2975

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1115

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 3:30 p.m. Day: 30 Month: 6 Year: 19 91

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Co. (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1145'

1st plug at 1145' with 50 sx cement,

2nd plug at 555' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
7-2-91
JUL 02 1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5 p.m. Day: 30 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1145' with 50 sx cement,

2nd plug at 555' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (I don't) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE JUL 19 1991

INV. NO. 32310

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 22 1991
month day year

NE NW NE Sec 26 Twp 18 S, Rg 18 East West

OPERATOR: License # 5027
Name: J. A. ALLISON
Address: 300 W. Douglas, Suite 305
City/State/Zip: Wichita, KS 67202-2975
Contact Person: J. A. Allison
Phone: (316) 263-2241

4950 feet from South line of Section
1650 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5122
Name: Woodman-Iannitti Drilling Co.

County: RUSH
Lease Name: DEIGHTON Well #: 2
Field Name: Rush Center South
Is this a Prorated Field? yes no

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 1985 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes ... no
Depth to bottom of fresh water: 200'
Depth to bottom of usable water: 550'
Surface Pipe by Alternate: 1 ... 2
Length of Surface Pipe Planned to be set: 1115'
Length of Conductor pipe required: None
Projected Total Depth: 3725'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
... well ... farm pond other

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

DWR Permit #: _____
Will Cores Be Taken? ... yes no
If yes, proposed zone: _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: _____

Exp. 10/4/91

AFFIDAVIT

570' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher R.24 wheel 562

SPUD DATE 6-24-91 INIT. CA

LENGTH SURFACE PLANNED 1150'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbs. when done bbbs.

RATHOLED AHEAD? Y SIZE HOLE _____
SURFACE PIPE 2 7/8 @ 1115 CONDUCTOR _____
ANHYDRITE T- B-1145 ELEVATION _____

TD 3833 FORMATION _____

RAN PIPE @ SX DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____

Arbuckle Plug @ _____ Ft. W/ SX

Hug./Council @ _____ Ft. W/ _____ SX

Anhydrite Base @ 1145 Ft. W/ 50 SX

1/2 Base Anhy. @ _____ Ft. W/ _____ SX

1/2, 1/2 Plug @ 555 Ft. W/ 50 SX

Bottom Surface @ _____ Ft. W/ _____ SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W K SX MOUSE HOLE W/ _____ SX

WATER WELL _____ SX (Irr. Well Pond _____)
Hauling _____

TECHNICIAN SR DATE 6-29-91

TYPE OF CEMENT 60/40 6%

STARTING TIME 5:30 (AM/PM) DATE 6-30-91

COMPLETION TIME 5:00 (AM/PM) DATE 6-30-91

CEMENT COMPANY Allied