

Toi 1 120524
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-21 130R
API NUMBER 19-165-21,542-0000
C/N/SENE, SEC. 26, T 18 S, R 18 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Operator: J.A. Allison
Name & Address 300 West Douglas, Ste 305
Wichita, Ka 67202

3630 feet from S section line
660 feet from E section line

Lease Name Tammen Well # 2
County Rush 122.03
Well Total Depth 3755 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1117

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drlg Co License Number 5122
Address Great Bend, Kansas

Company to plug at: Hour: 6⁰⁰ PM Day: 21 Month: 1 Year: 19 91

Plugging proposal received from Rich Wheeler
(company name) Woodman-Iannitti Drlg Co (phone) _____

were: Fill Hole @ mud & pump 50 sx cement @ 1145' through Drill pipe
Fill Hole @ mud & pump 60 sx cement @ 700' through Drill pipe
Fill hole @ mud & pump 10 sx cement @ 40' to the
Bottom of the cellar
Fill Rat hole @ 15 sx cement

1-25-91
IAN 25 1991

Anky 1110-37 Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ✓

Operations Completed: Hour: 8⁰⁰ PM Day: 21 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT

Filled Hole @ mud & pumped 50 sx cement @ 1145' through Drill pipe
Filled Hole @ mud & pumped 60 sx cement @ 700' through Drill pipe
Filled Hole @ mud & pumped 10 sx cement @ 40' to the bottom
of the cellar
Filled Rat hole @ 15 sx cement

Remarks: Cemented by Allied Cementing 60-40 Bag & 70 gal
(If additional description is necessary, use BACK of this form.)

INVOICED (If not observe this plugging.)

DATE 2-8-91
INV. NO. 30619

Signed Drew Rankin
(TECHNICIAN)