

15-165-02211-0000 10-18
1 120326

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/10/53
SE SE SE, SEC. 16, T 18 S, R 18 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Dirks Well # 1

Operator: Okmar Oil Company

County Rush 124.70

Name & Address Box 723

Well Total Depth 3837 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 915

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Okmar Oil Company License Number 5245

Address Box 723, Hays, KS 67601

Company to plug at: Hour: 3 p.m. Day: 18 Month: 10 Year: 19 89

Plugging proposal received from Ted Crawford

(company name) Okmar Oil Company (phone) 913-628-6101

were: 5 1/2" at 3826' Perfs at 3826-37'

1st plug pump in 5 1/2" casing with 600 lbs. hulls and 250 sx cement,

2nd plug pump in 5 1/2" X 8 5/8" annulus with 50 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4 p.m. Day: 18 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 600 lbs. hulls and 250 sx cement. Pumping pressure 0-1000 psi and shut in 900 psi.

2nd plug pumped in 8 5/8" X 5 1/2" annulus with 50 sx cement. Pumping pressure 0-200 psi and shut in 200 psi.

10-20-89

Remarks: Used 65/35 Pozmix 8% gel by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

(could observe this plugging.)

DATE 10-25-89

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 26231