

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-21498-6006

LEASE NAME Dean Barricklow

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 33 TWP. 20 RGE. 22 W or (W)

COUNTY Ness

Date Well Completed 8/78

Plugging Commenced 11/27/85

Plugging Completed 11/27/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

300 Sutton Place

ADDRESS Wichita, KS 67202

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Mailed with Application to Plug

Producing Formation Mississippi Depth to Top 4320 Bottom - T.D. 4356

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil	4350	56	8 5/8	463	none
Mississippi	oil & water	4336	38	5 1/2	4350	none
stage collar @	1413 with 230 SX	cement to surface.				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Displace 1 1/2 SX hulls & cement 4336 to 3886, Gel & 1/2 SX hulls 3886 to 1851, 135 SX cement 1851 to surface @ 200# final pump pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 300 Sutton Place, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jim Thatcher

(Address) 300 Sutton Place, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 85

Pauletta K. Engels  
Pauletta K. Engels Notary Public

My Commission Expires: 8-1-89



DEC 10 1985  
12-10-85  
COMMERCIAL RECORDS  
Wichita, Kansas

Form CP-4  
Revised 08-84