


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rush County. Sec. 19 Twp. 19S Rge. 20W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name Schlegel Well No. 1  
Office Address 801 Union Center Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 9 19 71  
Application for plugging filed May 9 19 71  
Application for plugging approved May 9 19 71  
Plugging commenced May 9 19 71  
Plugging completed May 9 19 71  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4408 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
|           |         | 0    | 252' | 8 5/8" | 252'   | None       |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug: 600'/70 sacks cement  
240'/20 sacks cement  
40'/10 sacks cement & 1/2 sack hulls

RECEIVED  
STATE CORPORATION COMMISSION  
5-25-71  
MAY 25 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Hellar Drilling Company, Inc.  
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
D. L. Hellar, Pres. of Hellar Drilling Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar, President  
339 Union Center Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of May, 19 71  
My commission expires March 25, 1972

Catherine Darcey  
Catherine Darcey Notary Public.

DRILLER'S LOG

COMPANY: Abercrombie Drilling, Inc., Wichita, Kansas 67202  
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202  
 LEASE: #1 Schlegel  
 LOCATION: SE SE SE 19-19S-20W, Rush County, Kansas  
 COMMENCED: May 1, 1971  
 COMPLETED: May 9, 1971  
 CASING: Set 8 5/8" Surface Casing @ 252'/175 sacks cement

|           |                      |
|-----------|----------------------|
| 0-135     | Surface Soil & Clay  |
| 135-580   | Shale                |
| 580-915   | Shale & Red Bed      |
| 915-950   | Sand                 |
| 950-1488  | Sand-Red Bed & Shale |
| 1488-1517 | Anhydrite            |
| 1517-1900 | Red Bed & Shale      |
| 1900-2307 | Shale & Lime         |
| 2307-2935 | Lime & Shale         |
| 2935-3135 | Shale & Lime         |
| 3135-3651 | Lime & Shale         |
| 3651-3825 | Lime                 |
| 3825-3950 | Lime (L.K.C.)        |
| 3950-4163 | Lime                 |
| 4163-4195 | Lime & Shale         |
| 4195-4317 | Lime                 |
| 4317-4355 | Lime & Shale & Sand  |
| 4355-4408 | Lime                 |
| 4408      | Rotary Total Depth   |

D & A


RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 25 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Schlegel, located in SE SE SE 19-19S-20W, Rush County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By D. L. Hellar  
 President - D. L. Hellar



Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of May, 1971.

Catherine Darcey  
 Notary Public - Catherine Darcey

My Commission Expires: March 25, 1972.