

15-165-00053-0000

16

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rush County. Sec. 10 Twp. 19S Rge. 20W

Location as "NE/CNW/SW" or footage from lines NE SW NW

Lease Owner Natural Gas and Oil Company

Lease Name Yost Well No. 1

Office Address P. O. Box 105 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 6 - 28 19 59

Application for plugging filed 7 - 12 19 60

Application for plugging approved 7 - 13 19 60

Plugging commenced 8 - 3 19 60

Plugging completed 8 - 13 19 60

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production July 31 19 60

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Cherokee Depth to top 4210 Bottom 4213 Total Depth of Well 4345 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	517	None
				5-1/2	4344	3670'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 8-3-60. Plugging completed 8-13-60.
Measured into total depth, 4343'. Plugged off bottom:
Pushed plug to 4175' and dumped 10' of sand and 4 sacks of cement. Worked and shot casing. Shot 5 1/2" casing at 3670'. Worked casing free. Built rack and slide. Pulled and laid down casing. Circulated and mixed 30 sacks of mud at 500'. Mixed 20 sacks of cement. Mudded to 180'. Mixed 20 sacks of cement at 180'. Mudded up to 40'. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
8-18-60
AUG 18 1960

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a/ Forbes Casing Pulling Company
Address P. O. Box 221 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
I, J. B. Steele, Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P. O. Box 105 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August 19 60

Richard R. Brack Notary Public.

My commission expires July 27, 1963



DRILLER'S WELL LOG

OPERATOR: NATURAL GAS & OIL CORPORATION
1009 Central Building
Wichita 2, Kansas

WELL NAME: #1 YOST
LOCATION: NE SW NW
Sec. 10-19S-20W
RUSH COUNTY, KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: June 11th, 1959

CASING RECORD: 8-5/8 @ 517' (300 sk cmt)
5 @ 4344' (100 sk cmt)

COMPLETED: June 24th, 1959

ELEVATION: 2194' KB

ROTARY TOTAL DEPTH: 4345'

PRODUCTION: UNKNOWN

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	250
Shale & Shells	300
Sand & Gravel	360
Shale	800
Sand	1010
Shale	1120
Shale & Red Bed	1422
Anhydrite	1451
Shale	2280
Lime	2485
Lime & Shale	2600
Lime	2805
Lime & Shale	3505
Lime & Shale	3725
Lime	3892
Lime & Chert	3932
Lime	4219
Sand	4243
Lime & Shale	4285
Sand	4325
Chert	4345
R.T.D.	4345

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1960

7-14-60
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 26 day of June, 1959

My Commission expires: August 11th, 1962. Patricia M. Edwards,

Notary Public.