


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Rush County. Sec. 10 Twp. 19 Rge. 20 (SW NE NW)
Location as "NE/CNW/SW" or footage from lines: SW NE NW
Lease Owner: Petroleum Inc.
Lease Name: Yost Well No. D # 1
Office Address: R. H. Garvey Bldg, 300 W. Douglas, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: March 5 19 76
Application for plugging filed: March 5 19 76
Application for plugging approved: March 5 19 76
Plugging commenced: March 5 19 76
Plugging completed: March 5 19 76
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Leo Massey
Producing formation: Depth to top: Bottom: Total Depth of Well: 4350
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 900' w/60 sacks cement thru drill pipe.
Middle plug @ 500' w/25 sacks cement thru drill pipe.
Top plug @ 40' w/1 sack hulls and 10 sacks cement
2 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Duke Drilling Co.
Address: Box 823, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON
Leonard Williamson (employee of owner) or (XXXXXXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 8th day of March 19 76

Notary Public: Gladys M. Hague

My commission expires April 11, 1978

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1976
3-10-76
CONSERVATION DIVISION
Wichita, Kansas

15-165-20576-0000

DRILLERS' WELL LOG

DATE COMMENCED: February 26, 1976
DATE COMPLETED: March 5, 1976

PETROLEUM, INC.
YOST D # 1
SW NE NW
Sec 10-T19-R20
Rush County, Kansas

ELEVATION: 2206 K.B.

| | |
|--------------|-----------------------|
| 0 - 295' | Surface Clay, Sand |
| 295 - 500' | Sand, Shale |
| 500 - 526' | Shale, Shells |
| 526 - 625' | Shale |
| 625 - 820' | Red Bed, Sand Streaks |
| 820 - 1090' | Sand |
| 1090 - 1429' | Red Bed |
| 1429 - 1466' | Anhydrite |
| 1466 - 1940' | Shale, Lime Streaks |
| 1940 - 3718' | Lime and Shale |
| 3718 - 3722' | Shale |
| 3722 - 3763' | Lime and Shale |
| 3763 - 4069' | Lime |
| 4069 - 4207' | Lime and Shale |
| 4207 - 4350' | Chert and Lime |
| 4350 - 4350' | RTD |

FORMATION TOPS

| | |
|-------------|------|
| Anhydrite | 1429 |
| Hoebner | 3718 |
| Kansas City | 3763 |
| Base K.G. | 4069 |
| Mississippi | 4207 |
| RTD | 4350 |

SURFACE PIPE:
Set 525' of 8 5/8", 20# new
pipe w/275 sacks 50/50 Pozmix,
2% Gel, 3% cc.

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1976
3-10-76
CORPORATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 9th day of March, 1976.

Deborah M. Hague
Notary Public

My Commission Expires: April 11, 1978