

STATE OF KANSAS
 KANSAS CORPORATION COMMISSION
 CONSERVATION DIVISION
 130 South Market - Room 2078
 Wichita, Ks. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-203-20,120-0000

LEASE NAME BRACK

WELL NUMBER #1

2040' Ft. from Section Line

2240' Ft. from Section Line

SEC. 25 TWP. 20S RGE. 35 (E) or (W)

COUNTY Wichita

Date Well Completed 6/8/95

Plugging Commenced 6/7/95

Plugging Completed 6/8/95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Suite 801 Wichita, Ks. 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-7-95 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top _____ Bottom _____ T.D. 50631

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | **CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill hole with heavy mud. 1st plug at 2275'-2075', 2nd plug at 1250'-930', 3rd plug at 690'-530', 4th plug at 290'-130', 5th plug at 40'-0'.

Name of Plugging Contractor Abercrombie RTD, Inc.

Address 150 N. Main, Suite 801 Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie RTD, Inc.

STATE OF Kansas COUNTY OF Sedgwick

Jack K. Wharton (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Ste 801, Wichita, Ks. 67202



SUBSCRIBED AND SWORN to before me this 23rd day of June, 1995

Rose Marie Smith
 Notary Public

My Commission Expires: 11-8-98

USE ONLY ONE SIDE OF EACH FORM

EFFECTIVE DATE: 5-24-95
DISTRICT # 1
SCA? Yes X No

State of Kansas
NOTICE OF INTENTION TO DRILL 203-20,120-~~0000~~
Must be approved by the K.C.C. five (5) days prior to commencing well.

FORM MUST BE SIGNED

Expected Spud Date .. May 22, 1995 ..
month day year
Spot E/2 .. SE .. NW .. Sec 25 .. Twp 20 .. S, Rg 35 .. X East

OPERATOR: License # 5422
Name: Abercrombie Drilling, Inc.
Address: 150 N. Main, Ste. 801
City/State/Zip: Wichita, Ks. 67202
Contact Person: Mark Galyon
Phone: 316)262-1841

2040' .. feet from South North line of Section
2240' .. feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Wichita
Lease Name: Brack .. Well #: 1
Field Name: White Woman NE
Is this a Prorated/Spaced Field? .. yes X .. no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 400'
Ground Surface Elevation: APPR. 3148' G.L. feet MSL
Water well within one-quarter mile: .. yes X .. no
Public water supply well within one mile: .. yes X .. no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1100' 1200'
Surface Pipe by Alternate: .. 1 .. X 2
Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: 0
Projected Total Depth: 5100'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
.. well .. farm pond X .. other

CONTRACTOR: License #: 30684
Name: RTD

Well Drilled For: Well Class: Type Equipment:
X Oil .. Enh Rec .. Infield X Mud Rotary
.. Gas .. Storage .. X Pool Ext. .. Air Rotary
.. OAWO .. Disposal .. Wildcat .. Cable
.. Seismic; .. # of Holes .. Other
.. Other ..
If OAWO: old well information as follows:
Operator: N/A
Well Name: ..
Comp. Date: .. Old Total Depth ..

Directional, Deviated or Horizontal wellbore? .. yes X .. no
If yes, true vertical depth: ..
Bottom Hole Location: ..

Will Cores Be Taken?: .. yes X .. no
If yes, proposed zone: ..

AFFIDAVIT 200' Alt. II Req. RECEIVED
KANSAS CORPORATION COMMISSION

Exp. 11/19/95
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

MAY 19 1995

- 1. Notify the appropriate district office prior to spudding of well;

Pusher Gary Fisher INIT. R-L
SPUD DATE 5-28-95
LENGTH SURFACE PLANNED 250' of 8 5/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 262' CONDUCTOR
ANHYDRITE T- 2257 B-2275 ELEVATION
5060
TD MISS FORMATION MISS
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Ingr./Council @ Ft. W/ SX
1 Anhydrite Base @ 2275 Ft. W/ 50 SX
2 1/2 Base Anhy. @ 1250 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 690 Ft. W/ 40 SX
4 Bottom Surface @ 290 Ft. W/ 40 SX
5 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W 15" SX MOUSE HOLE W/10 SX
WATER WELL SX (Irr. Well X Pond)
TECHNICIAN SP DATE 6-7-95 Hauling
TYPE OF CEMENT 60/4 Port 60% 4 Flu Seal
STARTING TIME 3:15 (AM/PM) DATE
COMPLETION TIME 6:15 (AM/PM) DATE 6-8
CEMENT COMPANY Allied