

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-203-20,095-0000

LEASE NAME Buerkle E

WELL NUMBER #1

4620' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 23 TWP. 20S RGE. 35 (E) or (W)

COUNTY Wichita

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-8-91

Plugging Completed 3-8-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sunburst Exploration Company, Inc.

ADDRESS 125 N. Emporia, Suite 112, Wichita, KS 67202

PHONE# (316) 262-3041 OPERATORS LICENSE NO. 5005

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-8-91 (date)

by Dwayne Rankin (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation Marm. & Mississippi Depth to Top \_\_\_\_\_ Bottom T.O. 5075

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	220'	None

RECEIVED  
4-9-91  
APR 09 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Fill w/heavy mud; set 1st plug @ 2250'-2050' w/50 sx; 2nd plug @ 1125'-925' w/50 sx; 3rd plug @ 575'-375' w/50 sx; 4th plug @ 240'-40' w/50 sx; 5th plug @ 40'-surface w/10 sx; rathole 15 sx; 60-40 pozmix 6% gel 1/4# Flocel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



Subscribed and sworn to before me this 8th day of March, 19 91  
Angela Woodard  
Notary Public

My Commission Expires: March 20, 1993

EFFECTIVE DATE: 2-20-91

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas 203-20,095

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 1 1991  
month day year

C NE NE Sec 23 Twp 20 S, Rg 35 East  
West

OPERATOR: License # 5005  
Name: Sunburst Exploration Company, Inc.  
Address: 125 N. Emporia, Suite 112  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Ron Irion  
Phone: (316) 262-3041

4620  
660 feet from South line of Section  
feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422  
Name: Abercrombie Drilling

County: Wichita  
Lease Name: Buerkle "E" Well #: 1  
Field Name: Wildcat  
Is this a Prorated Field? yes  no   
Target Formation(s): Marmaton & Mississippian  
Nearest lease or unit boundary: 660'  
Ground Surface Elevation: 3095' feet MSL  
Domestic well within 330 feet: yes  no   
Municipal well within one mile: yes  no   
Depth to bottom of fresh water: 880' 1150'  
Depth to bottom of usable water: 1150'  
Surface Pipe by Alternate: 1  2   
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: None  
Projected Total Depth: 5125'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
well  farm pond  other   
DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: yes  no   
If yes, proposed zone: \_\_\_\_\_

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... O&W ... Disposal  Wildcat ... Cable  
... Seismic; ... # of Holes

If O&W: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal Wellbore? yes  no   
If yes, total depth location: \_\_\_\_\_

Exp. 8/15/91

MAR 15 1991

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Shively  
SPUD DATE 2-27-91, INIT. S.D.  
LENGTH SURFACE PLANNED 200'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 3 1/2" @ 220' CONDUCTOR  
ANHYDRITE T-2222 B-45 ELEVATION 2095  
TD S125 FORMATION \_\_\_\_\_  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 2250 Ft. W/ 50 SX  
1/2 Base Anyh. @ 1125 Ft. W/ 50 SX  
1/2, 1/2 Plug @ 675 Ft. W/ 50 SX  
Bottom Surface @ 240 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN G.B. DATE 3-11-91 Hauling \_\_\_\_\_  
TYPE OF CEMENT 60-40-60 4 ft seal  
STARTING TIME 2:30 (AM/PM) DATE 3-8-91  
COMPLETION TIME 7:15 (AM/PM) DATE 3-8-91  
CEMENT COMPANY B J T. TAN  
608824