


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Wichita County. Sec. 11 Twp. 20S Rge. 35W (W)  
Location as "NE/CNW/SW" or footage from lines. C SW SE  
Lease Owner Leben Drilling, Inc.  
Lease Name Hester Well No. 1  
Office Address Box 486, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-31-67 19  
Application for plugging filed 8-31-67 19  
Application for plugging approved 8-31-67 19  
Plugging commenced 8-31-67 19  
Plugging completed 8-31-67 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey,  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5060 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				85/8"	450'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted @ 1980 100 sks. 50-50 Posmix, 6% gel through pipe  
@ 420' 25 sks. 50-50 Posmix through drill pipe  
Mud to 40', plug, 1/2 sk. hulls, 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1967  
9-5-67  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1967

My commission expires April 1, 1971  
Glauda Presbale Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc. etal  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: HESTER #1  
 LOCATION: C SW SE SECTION 11-20S-35W  
 WICHITA COUNTY, KANSAS  
 COMMENCED: 8-15-67 (Kelly's Water Well)  
 COMPLETED: 8-31-67

0	15	Topsoil, Clay
15	98	Sand, Clay
98	250	Shale
250	450	Shale
450	500	Blue Shale
500	1358	Clay, Shells
1358	1775	Shale, Shells
1775	2076	Shells, Shale
2076	2932	Lime, Shale
2932	5060	Lime
	<u>5060</u>	<u>RTD - D. &amp; A.</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION  
**SEP 5 1967**  
 CORPORATION DIVISION  
 Wichita, Kansas

8 5/8" used 28# surface casing set @ 450' cemented with 350 sacks of  
 Common, 2% cc  
 (Kelly's Water Well spudded the hole, Leben set surface)

I, Leslie Kite, do hereby certify that the above and foregoing is a  
 true and correct copy of the log of the Hester #1 Well, located C SW  
 SE of Section 11, Township 20 South, Range 35 West, Wichita County,  
 Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas, this 31st day of August, 1967.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:  
 April 1, 1971