


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 21 Twp. 31S Rge. 7 ~~XXX~~ (W)
Location as "NE/CNW/SW" or footage from lines W/2 W/2 SW/4
Lease Owner Jayhawk Oil Company
Lease Name Titus Well No. 1
Office Address 412 One Twenty Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-9 1963
Application for plugging filed 11-9 1963
Application for plugging approved 11-9 1963
Plugging commenced 11-9 1963
Plugging completed 11-9 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,711 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,711 feet (Rotary Total Depth to 240 feet. Set bottom plug at 240 feet and cemented with 20 sacks cement. Filled hole with heavy rotary mud to 35 feet. Set top plug at 35 feet and cemented with 10 sacks cement and 1/2 sack hulls - 2 sacks in rat hold.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
Priscilla M. Ismert Contractor
(employee of ~~owner~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Priscilla M. Ismert
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of November, 1963

My commission expires December 3, 1964.

Geraldine Hays
Geraldine Hays, Notary Public.



KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Jayhawk Oil Company**

SEC. **21** T. **31S** R. **7W**
 LOC. **W/2 W/2 SW/4**

FARM **Titus** NO. **1**

COUNTY **Harper**
 KANSAS

TOTAL DEPTH **4,711'**
 COMM. **10/24/63** COMP. **11/3/63**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED



CASING
 20 10
 15 8 **5/8"** 258' **con. w/200 sz.**
 12 6
 13 5

ELEVATION **1520 GR**
1522 DP
1525 KB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay w/sand streaks	100
Shale & Shells	1275
Shale & Lime	1775
Lime & Shale	2000
Shale w/lime streaks	2070
Shale & Shells	2440
Shale & Lime streaks	2600
Shale & Lime	3875
K. C. Lime	3715
Lime	4253
Shale & Lime	4275
Shale, Lime & Chert	4346
Cherty Lime	4549
Lime	4580
Shale & Lime	4660
Lime & Shale	4679
Shale & Sand	4711
Rotary Total Depth	4711

Sample Tops

Lansing	3813	-2288
Mississippi	4328	-2803
Base Mississippi	4579	-3054
Simpson Dolomite	4704	-3179
Rotary T. D.	4711	-3186

RECEIVED
 STATE CORPORATION COMMISSION

NOV 15 1963

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Frischilla M. Ismert
Frischilla M. Ismert

STATE OF KANSAS)
 SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 14th day of November, 1963.

Geraldine Hays
Geraldine Hays, Notary Public

My Commission Expires:
 December 3, 1964.