

15-077-20162-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County. Sec. 33 Twp. 31S Rge. 7W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

SE SE SW  
Lease Owner Okmar Oil Company  
Lease Name Bebermeyer #1 Well No.  
Office Address Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12/14/77 19  
Plugging completed 12/17/77 19  
Reason for abandonment of well or producing formation  
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens  
Producing formation Depth to top Bottom Total Depth of Well 4747  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	213	none
				5 1/2"	4744'	3212'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3900' and sanded to 3875', ran 5 sacks cement. Shot pipe at 3620', 3520', 3420', 3330', 3200', pulled 95 joints. Mudded hole to 270' and set 20' rock bridge, filled hole with 4 yards ready mix from 250' to base of cellar.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 22 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*  
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 77

My commission expires

MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

*Margaret Melcher*  
Notary Public.

DRILLERS' LOG

OKMAR OIL COMPANY  
No. 1 Bebermeyer  
SE SE SW, Sec. 33-31S-7W  
Harper County, Kansas

Commenced: 9-3-72  
Completed: 9-16-72

Elevation: 1459' K.B.

Surface Casing: 213.59' of 8-5/8"  
cemented w/225 sx cement, 3% cc.  
9-3-72

FORMATION

DEPTH

Surface Hole	0 - 219
Shale	219 - 660
Shale & Lime	660 - 1175
Lime & Shale	1175 - 3044
Shale & Lime	3044 - 3087
Sand	3087 - 3196
Lime & Shale	3196 - 3590
Sand	3590 - 3657
Lime & Shale	3657 - 3819
Lime	3819 - 4042
Lime & Shale	4042 - 4175
Lime	4175 - 4265
Lime & Shale	4265 - 4356
Lime	4356 - 4652
Shale & Lime	4652 - 4744
Lime	4744 - 4747 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 20th day of September 1972.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public

