

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER \_\_\_\_\_

LEASE NAME Williams #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C of NW SE

SEC. 35 TWP. 31S RGE. 7W (E) OR (W)

COUNTY Harper

DATE WELL COMPLETED \_\_\_\_\_

PLUGGING COMMENCED 9-16-83

PLUGGING COMPLETED 9-21-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 801 Union Center Wichita, Kansas 67202

PHONE #( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

CHARACTER OF WELL \_\_\_\_\_  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita

IS ACC-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 4775'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	302'	none
				5-1/2"	4773'	3630'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with sand to 4300' and ran 5 sacks cement, pushed plug to 4350'.  
Shot casing @3750', 3630' and pulled a total of 87 joints (3630") of 5-1/2" casing.  
Plugged well with 3 sacks hulls, 25 sacks gel, released plug and displaced with  
125 sacks cement. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050

ADDRESS Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, SS.


R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23rd DAY OF September, 1983

Irene Hoover  
NOTARY PUBLIC



MY COMMISSION EXPIRES: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1983  
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

OPERATOR:	Abercrombie Drilling
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	#1 Williams
LOCATION:	C NW SE Section 35-31S-7W Harper County, Kansas
COMMENCED:	March 25, 1980
COMPLETED:	April 9, 1980

---

0	350	Red bed	Set 8-5/8' at 302' with
350	1155	Red bed & Shale	225 sacks.
1155	2088	Shale	
2088	3004	Shale & lime	
3004	3377	Lime & shale	
3377	4032	Shale & lime	
4032	4140	Lime & shale	
4140	4271	Lime	
4271	4397	Lime & shale	
4397	4529	Lime	
4529	4740	Lime & shale	
4740	4778	Lime	
4778		TD	

---

We certify that the above foregoing is a true and correct copy of the log on the #1 Williams, C NW SE Section 35-31S-7W, Harper County, Kansas.

Union Drilling Co., Inc.

  
R. D. Messinger