

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15077-21077
API NUMBER ~~15-007-21,007-00-00~~

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Williams
WELL NUMBER #1
SPOT LOCATION C SW NE
SEC. 35 TWP. 31 RGE. 7 (E or W)
COUNTY Harper
Date Well Completed 4/9/85
Plugging Commenced 4/9/85
Plugging Completed 4/9/85

LEASE OPERATOR Energy Three, Inc.
ADDRESS P.O. BOX 1505, Great Bend, Ks. 67530

PHONE # (316) 792-5968 OPERATORS LICENSE NO. 5430

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? State Corporation in Wichita, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION
T.D. 4850

APR 20 1985

OIL, GAS OR WATER RECORDS

CASING RECORD OBSERVATION DIVISION
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Sand & Red Bed	0	228	8-5/8	223.50	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged as follows by Sun Cementing: 35sx @ 900', 35sx @ 275', built bridge 60', filled w/ 25sx, 10sx in rathole, 10sx in mousehole, 60/40 Poz, 2% gel, 3% CC, completed 7:30 PM 4/9/85, plugging orders from State Corporation Commission in Wichita.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Big-H Drilling, Inc. License No. 5148
Address 400 One Main Place, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wilber D. Berg (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wilber D. Berg

(Address) 400 One Main Place, Wichita, Ks.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. _____

SUBSCRIBED AND SWORN TO before me this 24 day of April, 1985

Sandra L. Mendoza
Notary Public

My Commission expires: 2/13/86

DRILLERS LOG

#1 Williams

CASING RECORD:

8-5/8" @ 223.50
w/ 200sx cement

COMPANY:

Energy Three, Inc.

DESCRIPTION:

C SW NE
Sec. 35-31S-7W

CONTRACTOR:

Big-H Drilling, Inc.

COMMENCED:

April 1, 1985

COMPLETED:

April 9, 1985

ELEVATION: 1471 GR

FORMATION

FROM

TO

REMARKS

Sand & Red Beds	0	228
Red Beds & Shale	228	1199
Shale & Lime	1199	1530
Lime & Shale	1530	1828
Shale & Lime	1828	2326
Lime & Shale	2326	2569
Shale & Lime	2569	3034
Lime & Shale	3034	3252
Shale & Lime	3252	3741
Lime & Shale	3741	4040
Shale & Lime	4040	4144
Lime & Shale	4144	4344
Shale & Lime	4344	4417
Lime & Chert	4417	4615
Shale & Lime	4615	4732
Lime & Shale & Sand	4732	4850
RTD		4850

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1985
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Big-H Drilling, Inc.

Cindy J. Romig
Cindy J. Romig

Subscribed and sworn to before me this 17th day of April, 1985.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY EXPI. DATE 2/19/86

Sandra L. Mendoza
Notary Public