

15-165-0037-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 28 Twp. 19 Rge. 19 (E) W (W)

Location as "NE/CNWKSWK" or footage from lines. C NW SE

Lease Owner Mull Drilling Co. Inc.

Lease Name Seltman Well No. 1

Office Address 670 Nl 4th, Natl. Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.

Date well completed 7-18-62 19

Application for plugging filed 7-18-62 19

Application for plugging approved 7-18-62 19

Plugging commenced 7:00 P.M. 7-18-62 19

Plugging completed 9:00 P.M. 7-18-62 19

Reason for abandonment of well or producing formation  
Dry hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4228' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with drilling mud to within 360' of surface. A plug put at this depth with 1/4 sack hulls and 25 sacks cement. Hole filled to within 40' of surface with a plug and 1/4 sack hulls and 10 sacks cement. Two sacks cement put in rat hole after bridging same. This completed plugging of hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 25 1962  
7-25-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. tools.

Address Same as above.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts  
Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1962

B. H. Salter  
Notary Public.

My commission expires October 16, 1965



WICHITA COUNTY PUBLIC LANDS

COMPANY: MULL DRILLING CO. ET AL. ROTARY DRILLING COMMENCED: 7-10-62  
 Wichita, Kansas

CONTRACTOR: MULL DRILLING CO., INC. ROTARY DRILLING COMPLETED: 7-19-62  
 Wichita, Kansas

CASING RECORD: 369' 8-5/8" w/ 200 gr. LOCATION: SECTION No. 1  
 130' SW of C NW SE  
 Section 18-19S-19W  
 RUSH County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

20"	Sand
200"	Clay
369"	Blue shale
1435"	shale w/ sand
1460"	Anhydrite
1745"	Shale
2130"	Sandy shale
2240"	Shale & lime
2490"	Sandy shale
3231"	Lime & shale
3362"	Shale & chalk
3537"	Sandy lime w/ shale
3650"	Lime & shale
3784"	Sandy lime & shale
4140"	Lime w/ shale
4167"	Sand & shale
4207"	Charcoal sand
4229"	Archeolite & fossiliferous

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 7-25-62  
 JUL 25 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING CO., INC.

*[Signature]*  
 \_\_\_\_\_  
 MULL DRILLING CO., INC.

STATE OF KANSAS  
 COUNTY OF SEQUOIA

Subscribed and sworn to before me on this 25th day of July, 1962.



*[Signature]*  
 \_\_\_\_\_  
 Notary Public

My Commission Expires: August 20, 1963.