

## WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

**Give All Information Completely**  
**Make Required Affidavit**  
**Mail or Deliver Report to:**  
**Conservation Division**  
**State Corporation Commission**  
**800 Bittling Building**  
**Wichita, Kansas**

## FORMATION PLUGGING RECORD

**Strike out upper line  
when reporting plug-  
ging off formations.**

NORTH


**Locate well correctly on above  
Section Plat**

Rush County. Sec. 27 Twp. 19 Rge. 19 (E) 19 (W)  
Location as "NE¼NW¼SW¼" or footage from lines. NW NE NW  
Lease Owner. Virginia Drilling Company, Inc.  
Lease Name. Dechant Well No. 1  
Office Address. 701 Brown Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole). Dry hole  
Date well completed. October 6 19 48  
Application for plugging filed. October 7 19 48  
Application for plugging approved. October 7 19 48  
Plugging commenced. October 7 19 48  
Plugging completed. October 7 19 48  
Reason for abandonment of well or producing formation. Dry

If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....yes.....

Section Flat

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough .....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4360 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Circulate heavy mud in hole. Placed #1 plug @ 240'. Mixed 15 sx cement and poured down through drilling pipe, then filled hole to 30' of top with heavy mud. Placed #2 plug @ 30'. Mixed and poured 10 sx of cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Virginia Drilling Company, Inc......  
Address.....701 Brown Building, Wichita 2, Kansas.....

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
S. A. Murphy (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. C. Murphy*  
701 Brown Building, Wichita 2, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1948  
*Wm. Lee Hawkins*

My commission expires.....2/5/49.

22-2625                      2-48—15M

-----  
Notary Public

27 19 1960

Well: Dechant #1 - NW NE NW Sec. 27-19S-19W, Rush County, Kansas  
 Company: Virginia Drilling Company, Inc.  
 Contractor: Virginia Drilling Company, Inc.  
 Commenced: September 16, 1948  
 Completed: October 7, 1948  
 Total Depth: 4360  
 Elevation: 2235

FORMATION	DEPTH	Set 8-5/8" csg. @ 273	CIRCULATE:
Gay	0-23		
Sand-shells	23-100		
Shale-shells	100-267		
Cement	267-272		
Shale-shells	272-330	● 3606	45 min.
Sand-shale	330-420	3622	45 min.
Shale-shells	420-430	3715	1 1/2 hr.
Sandy shale	430-460	3752	2 hrs.
Shale-shells	460-815	3836	1 1/2 hrs.
Sand-shells	815-1070	3939	1 1/2 hrs.
Shale-shells	1070-1165	4130	2 hrs.
Shale-shells-redbed	1165-1394	4135	3 hrs.
Anhydrite	1394-1425	4150	1 1/2 hrs.
Shale-shells	1425-1665	4160	2 hrs.
Redbed-shale-shells	1665-1885	4190	2 hrs.
Shale-shells	1885-2220	4195	2 hrs.
Lime	2220-2300		
Shale-shells	2300-2365		
Shale-lime	2365-2423		
Lime, sandy	2423-2435		
Lime, hard	2435-2450		
Lime-shale	2450-2540		
Lime	2540-2575		
Lime-shale	2575-2775		
Lime	2775-2870		
Lime, broken	2870-2940		
Lime, shale	2940-3050		
Lime	3050-3090		
Shale	3090-3140		
Lime, broken	3140-3220		
Shale-lime	3220-3295		
Lime	3295-3330		
Lime-shale	3330-3425		
Lime	3425-3455		
Shale	3455-3470		
Lime-shale	3535-3570		
Lime	3570-3605		
Lime-shale	3605-3670		
Shale	3670-3676		
Shale-Lime	3676-3722		
Lime	3722-4058		
Lime-shale	4058-4112		
Lime	4112-4130		
Conglomerate	4130-4154		
Shale & Sand spots	4154-4175		
Lime	4175-4360		

  

TOPS	
Heebner	3674
Lansing	3722
Base Kansas City	3984
Pennsylvanian Cong.	4104
Ordovician Cong.	4146
Arbuckle	4309
Jeff City	4349

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Dechant #1, located in the NW NE NW Sec. 27-19S-19W, Rush County, Kansas, was drilled to a total depth of 4360 feet. Same was plugged and abandoned.

Subscribed and sworn to before me this 13<sup>th</sup> day of October, 1948.

My commission expires February 5, 1949.

